



SC Occupational Safety and Health Administration

25 MOST FREQUENTLY CITED CONSTRUCTION STANDARDS

January 1, 2013- December 31, 2013

Rank	# Cited	Standard	Hazard Description
1	30	1926.501(b)(1)	Fall Protection – unprotected sides and edges/residential construction
2	29	1926.300(b)(2)	Unguarded reciprocating, rotating or moving parts of equipment
3	27	1926.602(a)(9)(i)	No audible alarms for material handling equipment
4	26	1926.451(g)(4)(i)	Inadequate guardrails on open sides and ends of scaffold platforms
5	19	1926.100(a)	Failed to provide head protection
6	19	1926.404(b)(1)(ii)	Failed to provide approved GFCI's
7	19	1926.404(f)(6)	No permanent and continuous path to ground from circuits, equipment and enclosures
8	18	1926.602(c)(1)(vi)	Failed to ensure industrial trucks meet design requirements of ANSI B56.1-1969
9	16	1926.602(a)(9)(ii)	Earthmoving equipment used when the rear view is obstructed
10	15	1926.152(g)(9)	No signs posted prohibiting smoking
11	15	1926.601(b)(4)	Vehicles operated with obstructed view
12	13	1926.405(b)(1)	Unused openings in cabinets, boxes, and fittings not effectively closed
13	13	1926.405(b)(2)	No covers provided for pull boxes, junction boxes, and fittings
14	12	1926.404(b)(1)(i)	Failed to use GFCI's or assured equipment grounding conductor program
15	12	1926.652(a)(1)	Failed to protect each employee in an excavation from cave-ins
16	11	1926.1053(b)(1)	Ladder side rails do not extend 3 feet above upper surface
17	10	1926.451(c)(2)	No scaffold base plates and mud sills or other adequate firm foundation
18	10	1926.501(b)(10)	No fall protection or employees working above 6 feet in residential construction
19	10	1926.501(b)(13)	No guardrail system, safety net system, or personal fall arrest system used
20	10	1926.501(b)(14)	No guardrail system, safety net system, or personal fall arrest system when on, at, above, or near wall openings
21	9	1926.451(e)(1)	Ladder not provided to access scaffold
22	9	1926.453(b)(2)(v)	No body belt when working from an aerial Lift
23	8	1926.1053(b)(8)	Failed to secure ladders to prevent accidental displacement
24	8	1926.701(b)	No guard provided for rebar
25	7	1926.304(f)	Failed to ensure woodworking tools meet the requirements ANSI 01.1-1961